City of Rehoboth Beach, DE

First Street Drainage Project

and

2017 Pavement Management Study



Presented by:

Alan Kercher, P.E.

The Kercher Group, Inc.

Drainage System in the "First Street Area"

Phase 1 - Installed in 2003 Phase 2 - Initial "Possibility" Investigation – 2003 Updated Cost Estimate – 2009

Updated Cost Estimate – 2017



Existing Drainage System Schematic





Not To Scale

Existing Drainage System Schematic



- Hydraulically Inadequate
 - Undersized Pipes
 - Inefficient: Many changes in direction and junction boxes which induce energy losses
 - Reduces Capacity
 - Reduces Velocity
 - Results in Sedimentation Build-up

• Existing Condition of Pipes

- No Investigation to Determine the Integrity of the Existing Pipe System
- From Park Ave. to Lake Ave., the pipes run between houses

Phase 1 – Installed in 2003



- Remove and Replace Existing Pipe From First St. to Lake Ave.
 - Designed to Handle Runoff from Phase 1 & Phase 2
 - StormCeptor was installed for Water Quality

Design

- Phase 1 Designed to provide Hydraulic Capacity to handle Runoff from both Phase 1 and Phase 2
- Phase 2 "Possibility" study to determine if the elevations would work for a piping system on First Street.

Phase 2

Columbia Ave. to Lake Ave.

Three Options



Option No. 1



Install New Pipe From Columbia Ave. to First St.

- Tie into 2003 Drainage Project
- Complete Removal of Existing Pipes From Columbia Ave. to Park Ave.
- Partial Removal of Pipes from Park Ave to PA. Ave.
- Seal Ends of Existing Pipes that are not removed.
- Cost Estimate: Approx. \$470K
- Notes:
 - No Investigation to Determine the Integrity of the Existing Pipes
 - Seal Ends of Unused Pipes or Should Pipes be Fully Sealed???

Option No. 2



- Install New Pipe From Park Ave. to Lake Ave.
 - Tie into 2003 Drainage Project
 - Partial Removal of Pipes from Park Ave to Lake Ave.
 - Seal Ends of Existing Pipes that are not removed.
- Cost Estimate: Approx. \$390K
- Notes:
 - No Investigation to Determine the Integrity of the Existing Pipes
 - Seal Ends of Unused Pipes or Should Pipes be Fully Sealed???

Option No. 3



- Install New Pipe on Park Ave. & Oak Ave.
 - Tie into 2003 Drainage Project
 - Partial Removal of Pipes from Park Ave to Oak Ave.
 - Seal Ends of Existing Pipes that are not removed.
- Cost Estimate: Approx. \$320K
- Notes:
 - No Investigation to Determine the Integrity of the Existing Pipes
 - Seal Ends of Unused Pipes or Should Pipes be Fully Sealed???

2017 Pavement Management Study



Why Manage Your Pavements?



But We Don't Maintain Roads Properly



© Kercher Engineering, Inc.

There needs to be a Better Method!



Pavement Management

Why Timing Is Critical?





Pavement Deterioration Accelerates with Time





© Kercher Engineering, Inc.

What is

Pavement Management?



Pavement Management

- Planning tool for Budgeting:
 - Rational, Schematic Approach to managing Pavements
 - Collects and monitors data on current pavement conditions
 - Determines Repair Strategies and Costs
 - Prioritizes (Optimizes) Selected Repairs
 - Produces a Work Plan for the Selected Budget



PMS Flow Chart





© The Kercher Group, Inc.

Network-Level Management

- Overall road system
- Approximate Costs
 - Average values: actual costs depend on many factors including project size
- "General" Work Plan
 - Based on Windshield Survey
 - Requires Project-Level Analysis to finalize
 - Detailed Scope of Work
 - More Accurate Budget



Analytics Matter

- AgileAsset's Pavement Analyst[™] was used for Analysis and Reporting
 - Utilizes Decision Trees to Select Cost-effective Repairs
 - Utilizes Performance Models to Predict the Future
 - Utilizes Multi-Constraint Integer Optimization
 - Selects the Unique Set of Projects to Optimally meet the defined Constraints
 - For these analyses, the only constraint was the annual budget
 - Selects the Optimal Set of Projects to provide the Highest Possible Benefit for the Allowable Budget



Developing a Budget

- Ran Four 10-Year Budget Scenarios
 - \$200,000/Yr.
 - \$300,000/Yr.
 - \$375,000/Yr.
 - \$450,000/Yr.



© The Kercher Group, Inc.

Current State of the Network

Element	Total			
Length (CL Miles)	18.8			
PCI	59.99			
Net Worth (\$)	\$20,605,816			
Backlog Cost (Unfunded Repairs)	\$6,595,564			

"Backlog Cost" is the current total amount of money required to fund all pavement repairs needed within the City's roadway network



Future Pavement Condition

Network Pavement Condition 10 Year Optimized Analysis





Future Backlog Cost



Net Savings/ROI

Scenario Name	PCI	Backlog Cost
Current Condition	59.99	\$6,595,564

			Baseline: \$200K per Year			
Scenario Name	2027 PCI	2027 Backlog Cost	Reduction in Backlog	Additional Investment	Net Savings	ROI
\$200K/YR	46.4	\$9,698,763	\$0	\$0	\$0	
\$300K/YR	53.3	\$8,496,049	\$1,202,714	\$1,000,000	\$202,714	1.20
\$375K/YR	59.2	\$7,358,315	\$2,340,448	\$1,750,000	\$590,448	1.34
\$450K/YR	63.5	\$6,442,340	\$3,256,423	\$2,500,000	\$756,423	1.30





Alan Kercher, P.E. <u>alan@kerchergroup.com</u> 302-894-1299 (direct line)

THE KERCHER GROUP, INC.

www.kerchergroup.com

